

積算

〇〇駅改良概算工事費算定表

工事種類	内訳	規格	昼夜区分	単位	単価(千円)	補正係数	終点方8.0m拡幅案		終点方8.0m拡幅案 (券売機移設集約案)		終点方15.0m拡幅案		終点方20.5m拡幅案		起点方11.0m拡幅案		
							数量	金額(千円)	数量	金額(千円)	数量	金額(千円)	数量	金額(千円)	数量	金額(千円)	
① 人口地盤・建物新設、JR駅舎改良工事																	
仮設工事	作業ヤード整備		昼間不良	m ²	10	1.1	528.5	5,814	528.5	5,814	528.5	5,814	528.5	5,814	768.9	8,458	
	仮囲い		昼間不良	m	33	1.1	66.0	2,360	66.0	2,360	66.0	2,360	66.0	2,360	86.2	3,082	
	ホーム上仮囲い		夜間不良	m	45	1.1	24.0	1,180	24.0	1,180	24.0	1,180	24.0	1,180	23.2	1,141	
	線路防護工		夜間不良	m	18	1.1	91.4	1,780	91.4	1,780	99.5	1,937	98.9	1,926	71.5	1,392	
	工事用ゲート		夜間不良	箇所	962	1.1	3.0	3,175	3.0	3,175	3.0	3,175	3.0	3,175	3.0	3,175	
	空頭防護工		夜間不良	箇所	1,280	1.1	1.0	1,408	1.0	1,408	1.0	1,408	1.0	1,408	1.0	1,408	
	木製覆工		夜間不良	m ²	125	1.1	108.0	14,850	100.0	13,750	124.0	17,050	124.0	17,050	496.0	68,200	
	アスファルト舗装		夜間不良	m ²	64	1.1	154.0	10,842	140.0	9,856	173.0	12,179	173.0	12,179	441.0	31,046	
	列車近接警報機		夜間不良	線	2,800	1.0	4.0	11,200	4.0	11,200	4.0	11,200	4.0	11,200	4.0	11,200	
	列車停止装置		夜間不良	線	3,060	1.0	4.0	12,240	4.0	12,240	4.0	12,240	4.0	12,240	4.0	12,240	
	軌道計測工	仮設撤去		夜間不良	m	377	1.1	240.0	99,528	240.0	99,528	260.0	107,822	260.0	107,822	320.0	132,704
		システム固定費		夜間不良	式	20,430	1.1	1.0	22,473	1.0	22,473	1.0	22,473	1.0	22,473	1.0	22,473
	横断配管		夜間不良	m	197	1.1	60.0	13,002	60.0	13,002	60.0	13,002	60.0	13,002	90.0	19,503	
	軌道整備		夜間不良	m	160	1.0	1200.0	192,000	1200.0	192,000	1300.0	208,000	1300.0	208,000	1600.0	256,000	
	既設建物撤去		昼間不良	m ²	20	1.0	540.0	10,800	540.0	10,800	540.0	10,800	540.0	10,800	540.0	10,800	
	保安費			%				20.0	80,530	20.0	80,113	20.0	86,128	20.0	86,126	20.0	116,564
	不確定要素			%				10.0	48,318	10.0	48,068	10.0	51,677	10.0	51,676	10.0	69,939
小計								531,500		528,747		568,445		568,431		769,325	
下部工	ホーム仮覆工		夜間不良	m ²	444	1.0	93.2	41,381	93.6	41,558	92.4	41,026	92.5	41,070	173.3	76,945	
	ホーム復旧		夜間不良	m ²	72	1.0	92.2	6,638	92.5	6,660	91.3	6,574	91.4	6,581	167.5	12,060	
	口元深礎準備工	φ1.5m	夜間不良	回	201	1.1	9.0	1,990	9.0	1,990	9.0	1,990	9.0	1,990	10.0	2,211	
	口元深礎準備工	φ3.0m	夜間不良	回	237	1.1		0		0		0		0	15.0	3,911	
	口元深礎工	φ1.5m	夜間不良	m	350	1.1	18.0	6,930	18.0	6,930	18.0	6,930	18.0	6,930	20.0	7,700	
	口元深礎工	φ3.0m	夜間不良	m	529	1.1		0		0		0		0	30.0	17,457	
	TBH杭準備工		夜間不良	式	2,340	1.1	1.0	2,574	1.0	2,574	1.0	2,574	1.0	2,574	1.0	2,574	
	基礎杭(TBH工)	φ1.0m	夜間不良	m	130	1.1	171.0	24,453	171.0	24,453	171.0	24,453	171.0	24,453	190.0	27,170	
	"	φ2.4m	夜間不良	m	507	1.1		0		0		0		0	285.0	158,945	
	保安費			%				20.0	16,793	20.0	16,833	20.0	16,709	20.0	16,720	20.0	61,795
	不確定要素			%				10.0	10,076	10.0	10,100	10.0	10,026	10.0	10,032	10.0	37,077
	小計								110,835		111,098		110,282		110,350		407,845
人工地盤	自由通路架設		夜間不良	m ²	370	1.0		0		0		0		0	487.8	180,486	
	人工地盤架設		夜間不良	m ²	370	1.0	411.3	152,181	364.3	134,791	505.3	186,961	505.3	186,961	1180.0	436,600	
	タワークレーン組立解体	JCC230H		夜間不良	回	36,000	1.4	1.0	50,400	1.0	50,400	1.0	50,400	1.0	50,400		0
		JCC400H		夜間不良	回	38,200	1.4		0		0		0		0		0
	V600C		夜間不良	月	37,900	1.4		0		0		0		0	1.0	53,060	
	口元深礎準備工	φ1.5m	夜間不良	回	201	1.1	4.0	884	4.0	884	4.0	884	4.0	884	4.0	884	
	口元深礎工	φ1.5m	夜間不良	m	350	1.1	8.0	3,080	8.0	3,080	8.0	3,080	8.0	3,080	8.0	3,080	
	基礎杭(TBH工)		夜間不良	m	130	1.1	76.0	10,868	76.0	10,868	76.0	10,868	76.0	10,868	76.0	10,868	
	タワークレーン損料	JCC230H		夜間不良	月	6,600	1.4	8.9	82,236	8.2	75,768	10.4	96,096	10.7	98,868		0
		JCC400H		夜間不良	月	8,300	1.4		0		0		0		0		0
	V600C		夜間不良	月	8,900	1.4		0		0		0		0	18.5	230,510	
	タワークレーン運転費	JCC230H		夜間不良	月	1,500	1.4	8.9	18,690	8.2	17,220	10.4	21,840	10.7	22,470		0
		JCC400H		夜間不良	月	1,500	1.4		0		0		0		0		0
	V600C		夜間不良	月	1,500	1.4		0		0		0		0	18.5	38,850	
	保安費			%				20.0	63,668	20.0	58,602	20.0	74,026	20.0	74,706	20.0	190,868
	不確定要素			%				10.0	38,201	10.0	35,161	10.0	44,416	10.0	44,824	10.0	114,521
	小計								420,208		386,774		488,571		493,061		1,259,727